

# Chermingat-Belumut-Tinggi Field Development

## PROJECT DETAILS:

Location:	Malaysia
Contract Value:	A\$30 million (2007)
Contract Period:	July 2007 - December 2007
Safety Statistics:	Manhours: 247,431 LTIFR: 8.09



## CLIENT: Intraline Resources

### Scope of Work:

Clough was awarded a contract in the form of a charter party from Intraline Offshore (Labuan) Ltd to carry out offshore installation activities for:

- **Newfield Peninsula Malaysia Inc** – East Belumut-A and Chermingat Pipelines (Contract No. P6016) which involved the installation of 20 kilometres of 10/4 inch piggy back pipelines (Chermingat) to BEL-A (East Belumut); the installation of 30 kilometres of 10 inch pipeline (BEL-A to TINGGI-A); and the installation of the 10 inch retrofit riser at Tinggi-A followed by Subsea tie-in spools.
- **Talisman Malaysia Limited** – PM-3 CAA Northern Field Development Project Contract No P60631 (Various Subsea spools installation at Talisman's PM3-CAA Bunga Orchid field involving 6 / 10 / 4 / 12 / 18 / 24 and 26 inch risers and sub-sea tie-ins. The scope included riser stalk on above water tie-in of the 24 inch and 26 inch at BO-D and BO-C)

Clough successfully completed its scope for Newfield Peninsula Malaysia Inc and in addition performed extra scope at Intraline's instruction. The extra scope included installation of conductors and pile annulus grouting at the Chermingat platform.

The Installation weather window allowed Clough to complete one 24 inch riser installation via davit lift method for Talisman Malaysia Limited prior to the monsoonal weather onset (December to February).

The *Java Constructor* demobilised in Singapore after more than 120 days of offshore work.